MYSORE DIVISION.

Dated 12th February 1931.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Mysore Division, up to 12th March 1931, for Restoration of the Chandre Minor Tank, Seringapatam Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of July 1931.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Mysore, between the hours of 11 A.M. and 5 P.M. on office days

3. Tenders should be submitted on printed forms, which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees one hundred in cash or Government Promissory Notes, as earnest money and be superscribed "Tender for Restoration of the Chandre Minor Tank, Seringapatam Taluk" in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The tendered rates will not be increased on any account.

10. Rates should be clearly quoted both in figures and words.

11. Lump sum rates at per cent below or above sanction will not be accepted.

Abstract estimate of Restoring Chandre Tank, Seringapatam Taluk.

Sl. No.	Items of work	Quantity	Per	Rates		Cost
				In words	In figures	
	Bund.					
1	Jungle clearing	16	Grade			
2	Cutting grips to bund	16	"			
3	Earthwork to bund including watering and tamping.	867	C.yd.			
4	Resetting old stone revetment with new jelli wherever necessary.	Lump	sum			
5	Turfing	108·00	Sqr.			
6	Providing and fixing grade stones including bed-stones.	17	each			
7	Top width stones including fixing ...	17	"			
8	Providing and fixing B. M. stones ..	2	"			
9	Do date and Register Number stone.	2	"			
10	Do gauge stone	1	"			
	Sluice at 43·00.					
1	Earthwork cutting and refilling bund including excavating foundations.	Lump	sum			
2	Concrete in surki mortar	467	C.ft.			
3	Providing cast iron pipe 6" dia. including carting and fixing, etc., complete.	7¼	Cwt.			
4	Burnt brick in surki mortar ..	555	C.ft.			
5	Burnt stone slabs dressed 6" thick ...	62	S.ft.			
6	Making holes in the slabs orifice coping and guide slabs.	3	No.			
7	Surki mortar plastering ..	4·87	Sqr.			
8	Cement plastering ..	0·75	"			
9	Teakwood plug with iron rod, etc., complete.	Lump	sum			

Sl. No.	Items of work	Quantity	Per	Rates		Cost
				In words	In figures	
	Waste weir at 50·00 (*Left.*)					
1	Earthwork excavation bund portion 50·00 soil to be used for flank bund.	Lump	sum			
2	Excavating foundation and using the earth to the flank bund.	·31	C.yd.			
3	Burnt brick in surki mortar ..	265	C.ft.			
4	Rough stone work with available stones	·46	C.yd.			
5	Burnt stone slabs 6" dressed ...	145	S.ft.			
6	Plastering with surki mortar ..	4·59	Sqr.			
	Waste weir at 50 00 (*Right*).					
1	Earthwork excavating bund for foundation, benching rock in central portion, cutting trench marti or stoney soil.	Lump	sum			
2	Burnt stone in surki mortar ...	1,274	C ft.			
3	Burnt stone slabs dressed 6" thick ...	130	S.ft.			
4	Plastering with surki mortar ...	9·23	Sqr.			

Dated 14th February 1931.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Mysore Division, up to 14th March 1931, for restoration of Narayanpur Dodkere, R. No. 94, Krishnarajpete Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of July 1931.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Mysore between the hours of 11 A.M and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees one hundred in cash or Government Promissory Notes as earnest money and be superscribed "Tender for restoration of Narayanpur Dodkere R. No. 94, Krishnarajpete Taluk, in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered, cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The tendered rates will not be increased on any account.

10. Rates should be quoted clearly both in figures and words.

11 L. S. rates at per cent below or above sanctioned will not be accepted.

Abstract estimate for restoring Narayanpur Dodkere Regr. No. 94 (Chinkurli Hobli), Krishnarajpete Taluk.

Sl No.	Items of work	Quantity	Unit	Rates		Cost
				In words	In figures	
	Bund R. L. 56·00					Rs.
1	Cutting grips to old bund	25	Grade			
2	Earthwork to bund including watering and consolidation.	3,150	C.yd.			
3	Turfing	285·86	Sqr.			
4	New stone work :—Rough stone revetment including jelly packing.	67	C.yd.			
5	Providing new grade stones including cutting figures and painting.	25	Each			
6	Providing Index stones	25	"			
7	Providing gauge stone including cutting figures and painting, etc., complete.	1	No.			
8	Providing B. M. stones including cutting figures and painting.	2	"			
9	Providing Register No. stone including cutting figures and painting, etc., complete.	1	"			
10	Removing and resetting old stone work including jelly packing, etc., complete.	1,135	C.yd.			
	Sluice.					
	Cut opening bund and refilling the same with necessary repairs to tunnel and cistern and closing up the leak in the sides of sluices.	Lump	sum Rs.			
	Waste weir R. L. 50·00					
1	Earthwork excavating foundation	19	Cyd.			
2	Stone jelly concrete in surki mortar	232	C ft.			
3	Burnt brick in surki mortar	193	"			
4	Plastering with surki mortar	2·64	Sqr.			
5	Rough stone work with new jelly packing, resetting Apron wherever necessary.	Lump	sum Rs.			

K. NARAYANA IYENGAR,
Executive Engineer.

OFFICE OF THE EXECUTIVE ENGINEER'S OFFICE, LOWER CHANNELS DIVISION, MYSORE.

Notice dated 30th January 1931.

The office of the Executive Engineer, Lower Channels Division, now located in the Double Overseer's Lodge at Nazarbad, Mysore, will be shifted to the late Mr. C. Venkata Rao's Bungalow, in the Mysore Yelwal Road, opposite the Public Offices, Mysore, and all communications, intended for that office, may, from the 1st of February 1931, be addressed as follows :—

The Executive Engineer,
Lower Channels Division,
Late Mr. C. Venkata Rao's Bungalow,
Opposite the Public Offices, Mysore.

N. KRISHNA IYENGAR,
Executive Engineer.

OFFICE OF THE ASSISTANT ENGINEER, No. 1, CHANNELS SUB-DIVISION, MYSORE.

Notification dated 31st January 1931.

As the office of the Assistant Engineer No. 1, Channels Sub-Division, Mysore, will be shifted to the Bungalow of late Mr. C. Venkata Rao, Mysore, Yelaval Road, Opposite to the Public Offices, Mysore, all communications intended for that office may be sent to this address from 2nd February 1931.

M. D. SRINIVASAIENGAR,
For *Assistant Engineer.*